

## SHF Series

### *Preterminated Stubbed Housings*

FET Series Fiber Entrance  
Terminal Compatible

Factory Terminated  
Cable Stub

Used for MDU Distribution  
Points, FTTH / FTTB



Fiber entrance terminal frames factory loaded with custom made fiber cable assembly.

#### KEY PRODUCT BENEFITS

- ▶ Factory terminated cable stub
- ▶ Constructed of superior materials capable of withstanding harsh outdoor environments, including UV degradation, chemical exposure, and extreme temperatures
- ▶ Meets GR-771 requirements



**Tii Technologies Inc.**

**Corporate Headquarters:**

141 Rodeo Drive  
Edgewood, NY 11717  
Phone: 631.789.5000  
Fax: 631.789.5063  
Toll Free: 888.844.4720  
sales@tiitech.com

# SHF Series

## SPECIFICATIONS

	FET1	FET2
<b>Typical Port Options</b>	1	6/12
<b>Product Series</b>	169F	506F
<b>Dimensions (LxWxH) (in.)</b>	6.2 x 4.4 x 2.6	10.3 x 10 x 3
<b>Packaging Dim. (in.)*</b>	20 x 20 x 15	20 x 20 x 15
<b>Shipping Weight (lbs.)*</b>	10	15

\* Estimated shipping size and weight based on 100ft of non-armored cable.

## CUSTOM MODEL NUMBER MATRIX

SHF	X	-X	X	X	X	X	X	-XX	XX	XXX	X
Chassis	Fiber Mode	# of Fibers	Cable Type	Fiber Type	Rating	Jacket Color	Panel Interface	Loose End	Length	UOM	
1 - FET1	R - Singlemode	1 - 1	C - SST Flat Drop (1-12F)	5 - 250um	R - Riser	2 - Orange	FC - FC	FC - FC	3 Digit e.g. 001	F - Feet M - Meters	
2 - FET2	N - SM G657A/B	2 - 2	D - Indoor Distr.	9 - 900um	P - Plenum	8 - Black	FA - FC APC	FA - FC APC			
	K - MM62.5 OM1	4 - 4	I - Indoor/Outdoor		N - OSP Dielectric	9 - Yellow	LC - LC	LC - LC			
	C - MM50 OM2	6 - 6	L - Loose Tube OSP		V - OSP Tenable	A - Aqua	SC - SC	OT - HFC			
	S - MM50 OM3	8 - 8					SA - SC APC	M1 - HFC			
		B - 12					ST - ST	M2 - HFC			
								SC - SC			
								SA - SC APC			
								ST - ST			
								NA - Pigtail			